The Mayor and Town Council of Georgetown

Department of Public Works
39 The Circle
Georgetown, DE 19947

Telephone (302) 856-6045
Fax (302) 855-5706
www.georgetowndel.com

Notice of Invitation to Bid

Notice is hereby given that sealed bids, in duplicate, will be received by the Town of Georgetown from a qualified firm for the milling and paving of West Laurel St. Proposals for will be received at the Town Hall, until 3:00 p.m. (EST) on **Monday, July 20, 2015.** At said time the proposals will be opened publicly.

It is strongly recommended that interested bidders visit the above mentioned street prior to submitting bids. Arrangements for a site visit can be made by calling Jeff Ward, Construction Coordinator, at 302-448-0542.

The right is reserved as the interest of the Town of Georgetown may appear, to reject any and all proposals, to waive any informality or irregularity in proposals received and to accept or reject any items of the proposal.

Bids must be made in accordance with the Invitation to Bid which is attached and made part of this notice.

Sincerely,

Jeff Ward

Construction Coordinator

The Mayor and Town Council of Georgetown

Department of Public Works
39 The Circle
Georgetown, DE 19947

Telephone (302) 856-6045
Fax (302) 855-5706
www.georgetowndel.com

Invitation to Bid

Sealed bids will be accepted by the Town of Georgetown, 39 The Circle, Georgetown, DE 19947 until 3:00 p.m. (EST) on Monday, July 20, 2015.

For general construction of: West Laurel St.

~~Bids are to include "Highway Construction" wage rate.~~ **(Updated 07/09/2015)**

Bids will be opened publicly.

Work includes Milling and Repaving of the following:

West Laurel St. – from North Front St. to Margaret St.

Description of work to include as follows:

1. Mill existing pavement to a depth of four (4) inches.
2. Construct butt joints at all tie-in areas to ensure elevations and positive drainage of new pavement.
3. Clean existing road surfaces free of loose debris.
4. Adjust existing utilities. (i.e. manhole frame and covers, valve box, etc.)
5. Apply tack coat to promote adhesion.
6. Apply two (2) inches of type "B" hot mix base course, machined rolled to prepared site.
7. Apply two (2) inches of type "C" hot mix surface course, machined rolled to prepared site.
8. Ensure positive drainage.
9. Work to begin within sixty (60) days after contract is awarded

The bidder agrees that this bid shall be good thru October 21, 2015 and may not be withdrawn after the scheduled closing time for receiving bids.

Contact William J Bradley (302) 856-6045 or Jeff Ward (302) 856 -7391 for any information pertaining to specifications of contract.

Sincerely,

Jeff Ward

Construction Coordinator